EROSION CONTROL NOTES 1. ALL CONSTRUCTION SHALL BE IN ACCORDANCE WITH STATE AND LOCAL REQUIREMENTS. 2. SUFFICIENT EROSION CONTROL PRACTICES MUST BE INSTALLED AND MAINTAINED TO RETAIN SEDIMENT WITHIN THE BOUNDARIES OF THE SITE. ALL DISTURBED AREAS SHALL BE NONEROSIVE AND STABLE WITHIN FIFTEEN (15) WORKING DAYS OR 90 CALENDAR DAYS AFTER COMPLETION OF THE ACTIVITY, WHICHEVER IS SHORTER. 3. MAINTENANCE: ALL EROSION AND SEDIMENT CONTROL PRACTICES TO BE INSPECTED WEEKLY AND AFTER EVERY RUNOFF PRODUCING RAINFALL EVENT. NEEDED REPAIRS WILL BE MADE IMMEDIATELY. GRADING CONTRACTOR IS RESPONSIBLE FOR EROSION CONTROL. 4. TOTAL DISTURBED AREA IS 2.1 ACRES. 5. SEE DETAIL SHEET FOR EROSION CONTROL DETAILS.

1. ALL STORM DRAINAGE PIPING SHALL BE NCDOT APPROVED HDPE.

2. UNLESS OTHERWISE NOTES, INSTALL ALL DRAINAGE PIPING AT A MINIMUM OF 3. SEE UTILITY PLAN FOR LOCATION OF PROPOSED WATER AND SEWER LINES. 4. ALL HDPE PIPING SHALL HAVE FLARED INLETS AND OUTLETS

5. CONTRACTOR SHALL CLEAR/GRUB A MINIMUM OF 60' WIDE RIGHT-OF-WAY FOR ALL STREETS AND ADDITIONAL AREAS FOR PONDS. 6. CONTRACTOR SHALL SCARIFY AND COMPACT SUBGRADE TO 100% OF STANDARD PROCTOR AT OPTIMUM MOISTURE CONTENT IN ACCORDANCE

WITH ASTM D-698. 7. CONTRACTOR SHALL PROVIDE A MINIMUM OF ONE (1) COMPACTION TEST FOR EVERY 10,000 SQUARE FEET OF 8-INCH LIFT. CONTRACTOR SHALL PROVIDE ONE (1) COMPACTION TEST PER 2,400 SQUARE FEET OF STONE BASE AFTER STONE DEPTH IS APPROVED BY THE ENGINEER. 8. CONTRACTOR SHALL PROOF ROLL ALL AREAS OF PROPOSED STREETS IN THE PRESENCE OF AN INDEPENDENT CERTIFIED TESTING LAB. ALL AREAS WHERE SUBGRADE IS NOT SUITABLE SHALL BE REMOVED AND REPLACED WITH SUITABLE MATERIAL AT CONTRACTOR'S EXPENSE. 9. ALL TESTING SHALL BE BY A CERTIFIED INDEPENDENT TESTING LABORATORY APPROVED BY THE ENGINEER. COPIES OF ALL LAB REPORTS SHALL BE FURNISHED TO THE ENGINEER WITHIN 96 HOURS OF THE TIME THE TEST

10. CONTRACTOR IS RESPONSIBLE FOR BALANCING CUT AND FILL ON SITE.

11. LOT DIMENSIONS PROVIDED BY OWNER.

12. TOPOGRAPHY SHOWN IS TAKEN FROM NCDOT LIDAR.

13. ALL CONSTRUCTION SHALL BE TO NCDOT STANDARDS. 14. INLET PROTECTION IS REQUIRED ON ALL STORM PIPING.

CONSTRUCTION SEQUENCE

1. OBTAIN GRADING PERMIT


2. INSTALL TEMPORARY MEASURES (CONSTRUCTION ENTRANCE, SEDIMENT DITCHES, SILT FENCING, AND SEDIMENT PONDS AS SHOWN ON THE APPROVED PLAN. TEMPORARY MEASURES SHALL BE IN PLACE PRIOR TO MAJOR CLEARING AND GRUBBING ACTIVITIES.

3. OBTAIN CERTIFICATE OF COMPLIANCE THROUGH ON-SITE INSPECTION BY NCDENR ENVIRONMENTAL INSPECTOR. 4. PROCEED WITH CLEARING AND GRUBBING AND GRADING OPERATIONS. 5. MAINTAIN DIVERSIONS AND OTHER MEASURES AS CONSTRUCTION PROGRESSES, CLEAN SEDIMENT TRAPS ONCE

SEDIMENT LEVEL REACHES HALF CAPACITY. 6. SEED AND MULCH DENUDED AREAS WITH 21 (THIRTY) DAYS AFTER FINISHED GRADES ARE ESTABLISHED. 7. MAINTAIN ALL EROSION CONTROL MEASURES UNTIL PERMANENT GROUND COVER IS ESTABLISHED AND REMOVAL

8. REQUEST FINAL APPROVAL BY ENVIRONMENTAL INSPECTOR. REMOVE ALL TEMPORARY EROSION CONTROL MEASURES AND STABLIZE THE AREAS.

5 FT. CONTOUR INTERVAL



EROSION CONTROL PLANS FOR: LAKESHORE LANDING UNITED STATES OF AMERICA W. KERR SCOTT RESERVOIR UNITED STATES OF AMERICALES
W. KERR SCOTT RESERVOIR _____